

2,500 tonne Dunbar Platform, Clydebank, Scotland.

Client: U.I.E. Scotland Ltd.



www.fagiolipsc.com

OFFSHORE 15



During the construction of the Dunbar Platform, Fagioli PSC utilised its Tower Lift system to perform the lift of the 2,500 tonne deck to allow a load out frame to be brought under.

The lift system utilised four number Fagioli PSC square format towers which each had a final height of approximately 16 meters with two PSC L600 jacks mounted at the top. Two L2/70D powerpacks positioned between each pair of towers provided the power for the synchronised lift.

