

# Lift of 7,000te Ampolex Integrated Deck, Far East Levingston Shipyard, Singapore

Client: Far East Levingston Shipyard



[www.fagiolipsc.com](http://www.fagiolipsc.com)

OFFSHORE 18



**Below left and below right:**

A cluster of six jacks and a cluster of four jacks mounted at the top of the support legs, with the powerpack positions immediately above.

**Above:** the deck in its final position after lifting with the load out frame underneath.

After weighing the 7,000te deck with our Flat Jack Weigh Packs, Fagioli PSC then performed the lift of the deck using twenty number Fagioli PSC L600 strand jacks mounted at the top of permanent legs.

Mounted in two groups of six and two groups of four, the jacks were powered by four number L12/8E powerpacks. The deck was lifted to an elevation at the top of the legs to allow the installation of a load out frame underneath.

